

TILLAMOOK COUNTY REWITNESS

#54

1/4 COR. SEC. 26 T 1 N R 10 W., WM.
35

HISTORICAL: GLO Pg. 4 IN 10 1857

BK.	Pg.	MAPS
1	371	B-419
10	133	B-749
53	76	


CONDITION GOOD FOUND: P.K. NAIL IN SPRUCE ROOT

FD. ROTTEN STUB	60" HEMLOCK	N. 24° W. 23 LKS	GLO Pg. 4
FD. ROTTEN STUB	24" HEMLOCK	S. 52° W. 23 LKS	GLO Pg. 4
* FD. GOOD NOW 26" ^{FACE} _{GROWN OVER}	24" HEMLOCK	N. 79 1/2° E 32 3/4 FT.	BK. 1 Pg. 371
* FD. GOOD NOW 34" ^{FACE} _{GROWN OVER}	23" HEMLOCK	S. 52 1/2° E 13 3/4 FT.	BK. 1 Pg. 371
FD 4" X 4" X 56" POST	ROTTED OFF; LAYED ALONGSIDE		MONUMENT

COMMENTS:

REWITNESS

1 SET 1 1/2" IRON PIPE WITH 3" BRASS CAP IN 10" CONCRETE CYLINDER
 @ POSITION OF OSBF P.K. IN X
 * 60" Hat Section 25' NORTH



NEW ACCESSORY:

COMMENTS: THIS CORNER IS LOCATED ± 500'
SW OF THE PP&L POWER LINES AND WLY OF A SMALL
CREEK (IN THE ROOT OF A SPRUCE TREE WHICH WAS SAWED
OUT IN ORDER TO SET THE MONUMENT)

IN THE PRESENCE OF: AL DVORAK DAN MCNUTT

DATE: 8-6-84

COB: _____

PHOTO#: _____

* = County corner tag affixed.

TILLAMOOK COUNTY REWITNESS TITLE